

**AGREEMENT IN LIEU OF AN EROSION AND SEDIMENT CONTROL
PLAN
FOR A SINGLE FAMILY RESIDENCE**



Land-Disturbing Permit No.: _____
Building Permit No.: _____
Subdivision: _____
Lot Number: _____

In lieu of submission of an erosion and sediment control plan for the construction of this single family residential dwelling, I hereby agree to comply with all requirements determined necessary by employees representing the Patrick County VESCP Administrator (County). Such requirements shall be based on the conservation standards contained in the Patrick County Erosion and Sediment Control Ordinance and the Virginia Erosion & Sediment Control Handbook (VESCH), and shall represent the minimum measures necessary to provide adequate control of erosion and sedimentation on or resulting from this project.

As a minimum, all denuded areas on the site shall be permanently stabilized within seven (7) days of reaching final grade or temporarily stabilized within 7 days for all denuded areas that may not be at final grade but will remain dormant for longer than 14 days (to include soil stockpiles). The type of temporary or permanent vegetation and or a protective ground cover shall be suitable for the time of year in accordance with the latest edition of the Virginia Erosion & Sediment Control Handbook (VESCH). Stabilization measures shall meet the requirements of VESCH 3.31 (Temporary Seeding); VESCH 3.32 (Permanent Seeding); and VESCH 3.35 (Mulching).

I further understand that a representative from the County will periodically inspect the site and will specify measures needed to comply and that failure to comply with such requirements following notice presented by any representative of the County could result in the issuance of a notice of violation of the Patrick County Erosion and Sediment Control Ordinance.

Additional Conservation Measures Specified by the County:

1. Adjacent streams, wetlands, and properties shall be protected from sedimentation by the installation of silt fence or other sediment filtering or sediment trapping measures specified or approved by the County. Sediment trapping or filtering measures shall be installed down grade of all disturbed/denuded areas and shall be installed in accordance with the applicable VESCH Specification.

2. A construction entrance in accordance with the VESCH Specification 3.02 will be installed where construction vehicles access a paved roadway. Where mud or sediment has been tracked onto the paved roadway the roadway shall be cleaned thoroughly. Mud or sediment shall be removed by shoveling first and then sweeping as necessary. Street washing of paved roadways shall only be allowed after all mud or sediment has been removed by first shoveling and then sweeping.
3. Construction Road Stabilization in accordance with the VESCH Specification 3.03 shall be applied to all areas that experience frequent construction traffic and parking. The Construction Road Stabilization shall be maintained in a condition that will prevent traffic and parking areas from becoming destabilized, and as a result, a source of sediment-laden stormwater runoff and or a source of mud and sediment tracked onto public roadways. Maintenance shall include the periodic addition of gravel to these areas in order to maintain them in a stabilized condition.
4. Soil stockpiles shall be stabilized and protected with sediment trapping measures. Acceptable stabilization measures shall be VESCH 3.31 (Temporary Seeding) and VESCH 3.35 (Mulching). Acceptable sediment trapping measures shall be VESCH 3.05 (Silt Fence).
5. Temporary erosion and sediment control measures shall be removed within 30 days after final site stabilization or after temporary measures are no longer needed, unless otherwise approved by the County. An assessment of final site stabilization shall be made by the County and temporary measures shall not be removed until after that assessment and subsequent approval by the County.
6. *Other measures may be specified on this form as deemed necessary by a County assessment of site specific conditions.*





PROPERTY OWNER

Printed Name of Owner: _____

Signature of Owner: _____ Date: _____

Party Responsible for Erosion and Sediment Control (If different from Property Owner):

Printed Name: _____

Signature: _____ Date: _____

PATRICK COUNTY VESCP AUTHORITY (COUNTY)

Approved By: _____ Date: _____

Mark A. Vernon, Combined ESC Administrator